



MKHAMBATHINI LOCAL MUNICIPALITY

REQUEST FOR QUOTATION

Advert Date 31 JANUARY 2019

The Mkhambathini Municipality invites eligible and accredited service providers to submit written quotations for installation of sewerage system at the learner's department.

The specification for sewerage system is attached on the pricing schedule:


Kindly note that they will be a site inspection on the 05th February 2019 at 10:00 am.

Quotations with the valid tax pin, CIDB grade 1CE/GB or higher, copy of CK1, proof of Central supplier database registration, original or certified valid BBEE Certificate and all MBD forms to be filled sealed in an envelope marked with quotation for installation of sewerage system, must be deposited during office hours, 08H00 to 16H15, Monday to Friday in the Tender Box of Mkhambathini Local Municipality, 18 Old main Road, Camperdown, 3720. The closing date for the above quotation will be **08 February 2019**.

The delivery date must be indicated. Quality of equipment quoted and budget available will be considered. The municipality has no obligation to appoint the lowest bidder.

For more information, please contact SCM officer on (031) 785 9338

Late and Faxed quotations will not be accepted.



Mrs. T.C Ndlela

**Municipal Manager
Mkhambathini Municipality**

QUOTATION FOR SEWERAGE SYSTEM OF THE LICENCING OFFICES

ITEM NO IN BILL	DESCRIPTION	UNIT	QTY	RATE (R)	TOTAL
SABS					
1	SEPTIC TANK				
1	Excavations of soft materials for toilet pit	m3	50.00		
	Backfilling	m3	10.00		
	spoil of surplus material	m3	40.00		
1.2	Brickwork 230mm with brick force every two course	m2	80.00		
1.3	Water proof on the septic tank walls	m2	70.00		
1.4	Concrete Blinding 15 Mpa	m2	18.00		
	30MPa Concrete Slab 150mm thicken for septic tank floor	m3	6.00		
1.6	30MPa Concrete Slab 150mm thicken for septic tank top slab with 2 openings for Manholes	m3	6.00		
1.7	Mesh Wire installation for septic tank floor slab REF 293	m2	17.00		
1.8	Installation of Reinforcement	ton	0.50		
1.9	Supply and install three Galvinised Steel covers	no.	3.00		
	Sockpit excation and backfill with hard rock and umngeni sand	sum	1.00		
1.1	Supply and install the pipes to link septic tank and sockpit	sum	1.00		
2	Sewer line pipes				
2.1	Excavations of soft materials for toilet pit	m3	60.00		
2.2	Backfilling	m3	35.00		
2.3	spoil of surplus material	m3	25.00		
2.4	Supply and install 110mm Diameter PVC Pipe with the bendings needed	m	80.00		
2.5	Remove and replace existing paving to prepare for excavations	m2	15.00		
2.6	Remove and replace existing parkhome at licencing Department	sum	1.00		
2.7	Clearing and Grabing on the area of existng Parkhome	sum	1.00		
1.4	Concrete Blinding 15 Mpa	m2	18.00		
1.6	30MPa Concrete Slab 150mm thicken for ParkHome Pantform with 293 Mesh Wire	m3	6.00		
TOTAL		NO.			
VAT	15.0%				
TOTAL					